


KANSAS

 STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Don Pratt Oil Operations,

Complete Address Drawer #370, Hays, Kansas.

Lease Name Ron Nickelson Well No. 1

Location NW-NW-SE Sec. 13 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 3765'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 10:30 AM Day 7 Month 9 Year 1970


The above well was plugged as follows:

169'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 100 Sx. cement thru
DP from 1175' to 850'. Pulled DP to 185' and displaced 25 Sx. cement thru DP from 185'
to 110'. Pulled DP, set bridge @ 40' with 1/3 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION
SEP 11 1970
CONSERVATION DIVISION
Wichita, Kansas

Signed: 
Well Plugging Supervisor

INVOICED

DATE 9/11/70
INV. NO. 2515-W