

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Don E. Pratt,

Complete Address Drawer #370, Hays, Kansas.

Lease Name Hildebrand Well No. A-1

Location NE-NE-NW Sec. 13 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4020'.

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.       

Operation Completed: Hour 10:45 AM Day 26 Month 6 Year 1969

The above well was plugged as follows:

184'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 1000'.

Circulated hole with heavy gel. Pulled DP to 1225' and displaced 100 Sx. cement thru  
DP from 1225' to 900'. Pulled DP to 210' and displaced 20 Sx. cement thru DP from  
210' to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
7-1-69

I hereby certify that the above well was plugged as herein stated.

INVOICED

CONSERVATION DIVISION  
Wichita, Kansas

Signed: [Signature]  
Well Plugging Supervisor

DATE 7-1-69

INV. NO. 27-W