

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7-23-1974
JUL 23 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Mobil Oil Corporation
Complete Address Box 1934, Oklahoma City, Oklahoma 73101
Lease Name Potter "A" Well No. 8
Location NE NW NE Sec. 29 Twp. 11 Rge. (E) (W) 16
County Ellis Total Depth 3340'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Glenn Pipe Pulling

Address Box 156, Ellinwood, Kansas 67526 License No. 686

Operation Completed: Hour 10 A Day 22 Month 7 Year 1974

The above well was plugged as follows:

- Total Depth 3340' 8 5/8 csg set at 939' ewc 450 sx.
- 5 1/2 csg set at 3337' ew 100 sk.
- Filled 5 1/2 csg W/sd (3340'-3300') dumped 5 sk cmt W/dump bailer. (3270'-3300')
- Cutoff & recovered 2700' of 5 1/2 csg.
- Filled 8 5/8 csg W/mud to 365' -set rock & sand bridge (365'-350')
- Filled with readymix cement from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 7/23/74
INV. NO. 9574-W