

15-051-02092-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
7-11-1974  
JUL 11 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Mobil Oil Corporation

Complete Address Box 1934 Oklahoma City, Okla. 73101

Lease Name Potter "A" Well No. 15

Location SE SE NE Sec. 29 Twp. 11 Rge. (E) (W) 16

County Ellis Total Depth 3390'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Glenn Pipe Pulling

Address Box 156 Ellinwood, Kansas 67526 License No. 686

Operation Completed: Hour 10 A Day 9 Month 7 Year 1974

The above well was plugged as follows:

Total Depth 3390' 8 5/8 csg set at 952' cwo 450' sk.

5 1/2 csg set at 3389' cw 150 sk cmt.

Filled 5 1/2 csg with sand to 3375' -dumped 4 sk cmt W/dump bailer. (3375-3345)

Cutoff and recovered App. 2500' of 5 1/2 csg.

Filled 8 5/8 csg with mud to ~~365'~~ set rock & sand bridge (~~365-350~~)

Filled with readymix cement from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo W. Wasey  
Well Plugging Supervisor

INVOICED

DATE 7/11/74

INV. NO. 9503-W