


15-051-02093-00-00



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 22 1974
7-22-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Mobil Oil Corporation
Complete Address Box 1934, Oklahoma City, Oklahoma 73101
Lease Name Potter "A" Well No. 16
Location NE NE NW Sec. 29 Twp. 11 Rge. (E) (W) 16
County Ellis Total Depth 3370'
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Glenn Pipe Pulling
Address Box 156 Ellinwood, Kansas 67526 License No. 686
Operation Completed: Hour 11:30 A Day 18 Month 7 Year 1974

The above well was plugged as follows:

- Total Depth 3370' 8 5/8 csg set at 957' cwc 475 sk.
- 5 1/2 csg set at 3369' cw 100 sk cmt.
- Filled 5 1/2 csg with sand (3350-3370) dumped 4 sk cmt W/dump bailer. (3350-3320)
- Cutoff and recovered 2646' of 5 1/2 csg.
- Filled 8 5/8 csg with mud to 365' -set rock & sand bridge (365-350)
- Filled with readymix cement from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED
DATE 7/23/74
INV. NO. 9566-W