

*W* KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 5 - 5 - 1964  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Davis Bros  
Complete Address: 510 Mc Farlin Bldg Tulsa, Okla  
Lease Name Chrisler Well No. 1  
Location CNW SE Sec. 36 Twp. 11 Rge. (E) (W) 16  
County Ellis Total Depth 3479  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated: \_\_\_\_\_  
Plugging Contractor: Barnes & Sons  
Address: Russell, Kansas License No. 9  
Operation Completed: Hour 3PM Day 3 Month 6 Year 64

The Above well, was plugged as follows:

8 5/8" 878' circulated with cement - 4 1/2" 3476' with 250 sax cement.  
Sand back to 2950', set 4 sax cement with dump bailer - pulled 2452'  
4 1/2" to 600', circulated hole with heavy gel mud through 4 1/2" ( 15 sax Gel)  
displaced 20 sax cement through 4 1/2" at 300', heavy mud to 160', displaced  
20 sax cement through 4 1/2" at 160', heavy mud to 35', set bridge and  
10 sax cement to 0'.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 6/5/64  
INV. NO. 9264-W

Signed: *Edon Petty*  
Well Plugging Supervisor