

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051--22,725-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Liberty Enterprises, Inc.

Complete Address 308 W. Mill, Plainville, Kansas 67663

Lease Name Arrowhead Well No. #1

Location N1 N1/2 E1 Sec. 31 Twp. 11 Rge. 16 (East) (West)

County Ellis Total Depth 3535'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Pioneer Drilling Company, Inc.

Address 308 W. Mill St., Plainville, Ks. 67663 License No. _____

Operation Completed: Hour: 3:45PM. Day: 4th Month: April Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8"-313' s.p. cuc. w/170 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 750' w/70 sacks of cement

2nd plug @ 310' w/40 sacks of cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks of cement

Circulate 10 sacks of cement in rat hole.

Amount of Surface Casing: 313' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

After giving these oral plugging orders I left to attend a plugging Seminar in Norman, Oklahoma so I was out of the state when this well was plugged. Mr. Aom phoned my residence and gave the plugging time as written above.

Signed: [Signature]
Conservation Division Agent

INVOICED
DATE 4-16-82
NO. 994-W

RECEIVED
STATE CORPORATION COMMISSION
4-12-1982
APR 12 1982
CONSERVATION DIVISION
Wichita, Kansas