

15-051-30363-00-00

Form CP-3
Rev. 6-26-62

14 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
CONSERVATION DIVISION
9-20-1966
SEP 20 1966
COMMUNICATIONS SECTION

Operator's Full Name Woodman-Iannitti Drlg. Co.

Complete Address: 706 Union National Building Wichita, Kansas

Lease Name Chrisler Well No. 1

Location NW NW SW Sec. 32 Twp. 11 Rge. 16 (E) (W) X

County Ellis Total Depth 3676

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 12- P Day 18 Month 9 Year 1966

The Above well was plugged as follows:

RTD 3676' 8 5/8 csg set at 222' cwc 140 sc.
Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced
25 sc thru drill pipe. Heavy mud to 210' set cementing plug and displaced
20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug. 1/3 sc
hulls and 8 sc cement to base of celler. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 9/20/66
INV. NO. 3960-11