

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22,692-00-00

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Discovery, Inc.

Complete Address P. O. Box 576, Great Bend, Ks. 67530

Lease Name D. Chrisler Well No. #1-36

Location NW-NW-NW Sec. 36 Twp. 11 Rge. 16 (East) (West)

County Ellis Total Depth 3475'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allen Drilling Company

Address P. O. Box 1389, Great Bend, Ks. 67530 License No. \_\_\_\_\_

Operation Completed: Hour: 5:00AM. Day: 26th Month: Nov. Year: 19 81

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

8 5/8" - 428' s.p. cnc. w/225 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 420' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks of cement

Circulated 10 sacks of cement in rat hole.

STATE CORPORATION COMMISSION

11-30-1981

I hereby certify that the above plugging instructions were given as herein stated.

12-10-81  
8613W

Signed: [Signature]  
Conservation Division Agent