

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 13 Twp. 9S Rge. 24W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW

Lease Owner Imperial Oil Company

Lease Name Nickelson "D" Well No. 1

Office Address 780 Fourth Natl. Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed October 27, 1962 19

Application for plugging filed October 27, 1962 19

Application for plugging approved October 27, 1962 19

Plugging commenced October 27, 1962 19


Plugging completed October 27, 1962 19

Reason for abandonment of well or producing formation

No commercial quantities of oil found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4030 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing	8-5/8" at 181'			Not pulled		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set first plug at 500' with 20 sacks cement

Set second plug at 175' with 15 sacks cement

Set top plug at 40' with 10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION  
11-16-62  
NOV 17 1962

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil of Kansas, Inc.

Address Box 97, WaKeeney, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

John Lehman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John Lehman

780 Fourth Natl. Bldg., Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of November, 1962

My commission expires July 5, 1966

Bette J. Silcott Notary Public.



DRILLER'S LOG

Imperial Oil Company  
780 Fourth National Building  
Wichita, Kansas

NICKELSON "D" NO. 1  
SE SE SW Sec. 13-9S-24W  
Graham County, Kansas

Total Depth: 4030'

Commenced: 10/19/62 Completed 10/27/62

Contractor: Imperial Oil of Kansas, Inc.  
Wichita 2, Kansas

Elevation: 2459 K.B.  
Production: dry

Casing Record: Set 8-5/8" surface pipe at 181' with 150 sacks cement

Figures indicate bottom of formations:

Rock & Sand	90'
Shale	1085'
Shale & Shells	1645'
Dakota Sand	1840'
Red Bed	1875'
Shale	2096'
Anhydrite	2132'
Shale	2190'
Shale & Shells	2420'
Lime & Shale	3772'
Lime	3822'
Lime & Chert	3862'
Lime	4030'

	<u>Sample Tops</u>	
Anhydrite	2096	(+363) (Drillers)
Heebner	3763	(-1304)
Toronto	3791	(-1332)
Lansing	3804	(-1345)
Base/90	4027	(-1568)

**RECEIVED**  
STATE CORPORATION COMMISSIONER

NOV 13 1962

CONSERVATION DIVISION  
Wichita, Kansas

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

By Raymond R. Dombaugh  
Raymond R. Dombaugh

Subscribed and sworn to before me this 15th day of November, 1962

My Commission Expires:

July 5, 1966

Bette J. Silcott  
Bette J. Silcott, Notary Public