

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-21,137-0001

LEASE NAME Hildebrand

WELL NUMBER A-1

SPOT LOCATION SW NE NW

SEC. 13 TWP. 9 RGE. 24W (E) or (W)

COUNTY Graham

Date Well Completed _____

Plugging Commenced 4-14-86

Plugging Completed 4-16-86

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ron's Oil Operations, Inc.

ADDRESS Rt. 1 Box 112 Penokee, Kansas 67659

PHONE # 913, 674-2409 OPERATORS LICENSE NO. 6861

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4035'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	226'	none
				4-1/2"	4008'	1846'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3800' and 4 sacks cement. Shot pipe @2418', 2040', 1846' and pulled a total of 47 joints (1846') of 4-1/2" casing. Plugged surface with 6 hulls and 250 sks. econolite mix. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address P.O. Box 347 Chase, Kansas 67524


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso
(Address) P.O. Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 22 day of April, 1986

My Commission expires:



Irene Hoover
Notary Public