

15-065-01613-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER Spud 5-1-57

LEASE NAME Nickelson

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 15 TWP. 9S RGE. 24W (E) or (W)

COUNTY Graham

LEASE OPERATOR Ron's Oil Operations, Inc.

ADDRESS RR1 Box 194 Penokee, KS 67659

PHONE # (913) 674-2315 OPERATORS LICENSE NO. 6861

Date Well Completed

Character of Well Oil

Plugging Commenced 1-6-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-14-94

The plugging proposal was approved on (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4058'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	193'	none
				5 1/2	4058'	700'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Sanded bottom to 3940' & 5 sks cement. Shot @ 2110 & 1231 - tight. Shot @ 903' - tight.
Pumped 125 sks w/250# hulls & displaced to 750'. Shot @ 700, pulled to 550. Circulated 100 sks w/250# hulls to surface. Pulled rest of pipe, topped off well. 65/35 pos 10% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ron's Oil Operations, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 28th day of January, 19 94

 IRENE HERZBERG
State of Kansas
My Comm. Expires Aug. 24, 1997

Jim Herzberg
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
1-31-94
JAN 31 1994
CONSERVATION DIVISION
Wichita, Kansas