

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-065-01615-0000

API NUMBER Spud 5-19-58

LEASE NAME Nickelson

WELL NUMBER A-3

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 15 TWP. 9S RGE. 24W (E) or (W)

COUNTY Graham

Date Well Completed

Plugging Commenced 1-17-94

Plugging Completed 1-18-94

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Ron's Oil Operations, Inc.

ADDRESS RR1 Box 194 Penokee, KS 67659

PHONE (913) 674-2315 OPERATORS LICENSE NO. 6861

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4037'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	220'	none
				5 1/2	4037'	650'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom @ 3912' & ran 5 sks cement. SHot @ 2100 & 1250. Pumped 125 sks w/250# hulls down to 800'. Shot @ 750, didn't come free. Shot @ 650, came free. Pulled 5 joints & pumped 80 sks w/200# hulls & circulated to surface. Pulled rest of pipe, topped off w/20 sks. 60/40 pos 10% gel. Plugging complete.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ron's Oil Operations, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 28th day of January, 1994

Irene Herzberg
 Notary Public

My Commission Expires:



RECEIVED
 STATE CORPORATION COMMISSION
 JAN 31 1994
 1-31-94
 CONSERVATION DIVISION
 Wichita, Kansas

IMPERIAL OIL ANSAS, INC.
Well Completion Report

Nickelson Lease. Well No. A-3
 Loc. SE NW NE Sec. 15 Twp. 9S Rge. 24W
 County Graham State Kansas
 Pool Holley South

Spud Date 5-10-58
 Rotary Completed 5-28-58
 Completion Date 6-6-58
 Potential
 Gravity
 R. T. D. 4037

Surface casing set at (8 5/8) 220 with 150 sacks
 Production casing set at (5 1/2) 4037 with 125 Sacks

Formation Tops: 2483 KB Sample Electric Log

Anhydrite	2138 (+ 345)	
Heebner	3774 (-1291)	3775 (-1292)
Toronto	3798 (-1315)	3800 (-1317)
Lansing	3816 (-1333)	3818 (-1335)

PRODUCING AND PROSPECTIVE PRODUCING ZONES

Formation	Depth	Feet	Remarks	Estimated Reserves
Lansing				23,600
35' Z	3847-52	5	DST 3836-52 2 hrs. Rec. 90' HOOM BHP 1325#	
160' Z	3973-77	4	Perf. 3972-75	
180' Z	3990-92	2	Perf/ 3992-96	

EXHIBIT "B"

RECEIVED
STATE OIL AND GAS COMMISSION

NOV 17 1958

Oil and Gas Division
Wichita, Kansas