


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Graham County. Sec. 15 Twp. 9S Rge. 24WE/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines \_\_\_\_\_  
C E/2 SW SE  
Lease Owner Tomlinson Oil Company  
Lease Name NICKELSON Well No. 1  
Office Address 200 W. Douglas, Suite 1030, Wichita, KS  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Dry Hole  
Date Well completed Jan. 14 19 80  
Application for plugging filed (verbally) Jan. 14 19 80  
Application for plugging approved (verbally) Jan. 14 19 80  
Plugging commenced Jan. 14 19 80  
Plugging completed Jan. 14 19 80  
Reason for abandonment of well or producing formation \_\_\_\_\_  
No commercial quantity of oil or gas encountered  
If a producing well is abandoned, date of last production \_\_\_\_\_  
19



Locate well correctly on above  
Section Plot

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4055'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

T.D. 4055'  
Set 1st plug at 1000' with 70 sacks  
2nd plug at 300' with 20 sacks  
3rd plug at 40' solid bridge with 10 sacks  
rathole with 5 sacks.  
Cemented with 50/50 posmix, 6% gel.  
Plug was down at 3:30 p.m., 01-14-80.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of January, 19 80



My commission expires 08-21-82

Sherrie L. Brooks Notary Public.  
STATE CORPORATION COMMISSION

1-18-80  
JAN 18 1980

CONSERVATION DIVISION  
Wichita, Kansas

CONTRACTOR'S WELL LOG

OPERATOR: Tomlinson Oil Company  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: Nickelson #1  
 LOCATION: C E/2 SW SE, Section 15-9S-24W  
 Graham County, Kansas  
 SPUD DATE: January 07, 1980  
 COMPLETION DATE: January 14, 1980

0	75	Surface clay and shale
75	312	Shale and sand
312	1274	Shale
1274	1622	Shale and sand
1622	1688	Shale
1688	1840	Sand
1840	2133	Shale
2133	2170	Anhydrite
2170	2565	Shale
3565	3240	Shale and lime
3240	3640	Lime
3640	3830	Shale and lime
3830	4055	Lime
	4055	Rotary Total Depth.

Spud hole at 10:00 p.m., January 07, 1980. Drilled 312' of 12 3/4" hole. Ran 7 joints of 8-5/8" - 24# casing. (Talley 314.13'). Set at 319' K.B. with 225 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 8:00 a.m., January 08, 1980.

T.D. 4055'. Set 1st plug at 1000' with 70 sacks, 2nd plug at 300' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 3:30 p.m., January 14, 1980.

SAMPLE TOPS:

Anhydrite 2133'  
 B/Anhydrite 2170'

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 18 1980

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

CONSERVATION DIVISION  
 Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Nickelson #1, C E/2 SW SE, Section 15-9S-24W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
 Jack L. Partridge  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me a Notary Public, in and for the county and state aforesaid, as of this 17th day of January, 1980.



Sherrie L. Brooks  
 Sherrie Brooks, Notary Public

My commission expires 08-21-82.