


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Graham County, Sec. 14 Twp. 9 Rge. 24 (E) (W)X
Location as "NE/CNWxSWx" or footage from lines SE/SE/NW
Lease Owner F & M Oil Co., Inc.
Lease Name NICKELSON Well No. 1
Office Address 603 Union Center Bldg. Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved October 19, 19 73
Plugging commenced December 1, 19 73
Plugging completed February 4, 19 74
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation Depth to top Bottom Total Depth of Well 4000 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	185	None
				5 1/2"	3999	Approx. 1133'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed a plug to 3800'. Dumped sand to 3775' and 5 sacks cement.
Shot casing at 3312, 2533, 2031, 1541, 1217 and 1133 ft. Laid down 26
joints of 5 1/2" casing. Squeezed well with 5 sacks hulls, 35 sacks gel,
150 cubic feet 50/50 Pozmix with 6% added gel.

RECEIVED
STATE CORPORATION COMMISSION
2-6-74 FEB 6 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.
Address Box 698 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



CATHY MILLER
NOTARY PUBLIC
Barton County, Ks.

(Signature)

James W. Rockhold

Box 698 Great Bend, Ks. 67530
(Address)

James W. Rockhold

SUBSCRIBED AND SWORN to before me this 5th day of February, 19 74

Cathy Miller
Cathy Miller Notary Public.

My commission expires September 30, 1975

T. WOODMAN
H.S. PHONE AM 5-3572
OFFICE PH. AM 5-7650
WICHITA, KANSAS

15-065-20436-0000

D. J. IANNITTI
TELEPHONE 653-2381
HOISINGTON, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY

Rotary Drilling Contractors

706 UNION NATIONAL BUILDING

WICHITA, KANSAS 67202

April 20, 1971

Company;	Falkowski & Messinger
Farm;	#1 Nickelson
Location;	SE SE NW
Section;	14-9-24W
County;	Graham
Comm;	April 8, 1971
Compl;	April 16, 1971
Total Depth;	4000'
Casing;	8 5/8" @ 184 w/130 sx. 5 1/2" @ 3999' w/100 sx.

RECEIVED
STATE CORPORATION COMMISSION

AUG 7 1974
CONSERVATION DIVISION
Wichita, Kansas

Figures Indicate Bottom Of Formations:

100	Clay & Sand
185	Shale
1100	Shale
1320	Sand & Shale
1600	Red Bed & Shale
1750	Sand
1900	Red Bed
2071	Red Bed
2109	Anhy
2365	Shale & Shells
2575	Shale & Shells
2830	Lime & Shale
2990	Lime
3095	Shale & Lime
3235	Lime
3365	Lime
3490	Lime & Shale
3590	Lime
3695	Lime
3785	Lime
3835	Lime
3854	Lime
3900	Lime
3930	Lime
3955	Lime
3974	Lime
4000	Lime

I certify the above to be a true and correct copy of the driller's log and the geological tops to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.

K. T. Woodman