


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 14 Twp. 9 Rge.      (E) 24 (W)  
Location as "NE/CNW&SW&" or footage from lines SW SE  
Lease Owner Vaughan Drilling, Inc.  
Lease Name Nickelson Well No. 1  
Office Address Box 825, 1314 Kansas, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed May 7 19 64  
Application for plugging filed May 20 19 64  
Application for plugging approved 19       
Plugging commenced 12:30 p.m. May 7, 1964 19 64  
Plugging completed 2:30 p.m., May 7 19 64  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19       
Was permission obtained from the Conservation Division or its agents before plugging was commenced? XXXXXXXXXX yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation      Depth to top      Bottom      Total Depth of Well      Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0'	187'	8 5/8"	187	none'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

Bottom plug @ 540' with 20 sx cement., Middle plug @ 180' with 1/4 sack hulls & 20 sacks cement., Top plug @ 40' with 1/2 sx hulls and 10 sx cement, 2 sacks in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION  
5-22-64  
MAY 22 1964  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor VAUGHAN DRILLING, INC.  
Address same as above

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Wayne Dobbs (~~employee~~) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne Dobbs  
VAUGHAN DRILLING, INC., by: Wayne Dobbs, V-Pres.  
Box 825, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of May, 1964

My commission expires Jan. 24, 1968

Dorothy Tully  
Dorothy Tully Notary Public.

WELL LOG

COMPANY	Vaughan Drilling, Inc.
CONTRACTOR	Vaughan Drilling, Inc.
FARM	#1 Nickelson
LOCATION	SW SE of section 14-9-24W Graham County, Kansas
Elevation	2408 K. B.
SURFACE PIPE	187' of 8 5/8" cemented with 150 sx posmix sunset.
PRODUCTION	D & A:
COMMENCED	April 28, 1964
COMPLETED	May 7, 1964

<u>FORMATION</u>	<u>DEPTH</u>
Sandstone & Clay	50
Shale	187
Grey Shale	300
Shale with sand streaks	430
Shale & Shells	600
Shale (grey)	710
Shale & Shells	800
Shale	990
Shale & Sand w/sand streaks	1410
Red Bed	1430
Shale & Shells	1600
Sandstone	1790
Shale & Shells	2040
Anhydrite	2088
Shale & Limestone	2325
Shale & Shells	2585
Shale & Limestone	2865
Limestone	2945
Limestone & Shale	3505
Limestone & Shale & Chalk	3705
Limestone & Shale	3765
Limestone	3970
Limestone & Shale	3980
RTD	3980

FORMATION TOPS

Anhydrite	2040 (+ 368)
Heebner	3712 (-1304)
Toronto	3736 (-1328)
Lansing	3550 (-1342)
RTD	3980 (-1572)

A F F I D A V I T

STATE OF KANSAS, COUNTY OF BARTON, SS:

I, Wayne Dobbs of the VAUGHAN DRILLING, INC., being first duly sworn on oath, state; that I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Wayne Dobbs  
WAYNE DOBBS, VICE-Pres.

Subscribed and sworn to before me this 21st day of May, 1964.

Dorothy Tuzly  
Dorothy Tuzly, Notary Public

My commission expires: Jan. 24, 1968.

Stamp: MAY 22 1964  
CONTRACTOR DIVISION  
MICHIGAN