


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 14 Twp. 9 Rge. (E) 24 (W)
Location as "NE/CNW/SW" or footage from lines C SW NW 1/4
Lease Owner Herman Geo. Kaiser, Oil Producer
Lease Name Kline Well No. /
Office Address 909 Palace Bldg. Tulsa Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed March 18 1958
Application for plugging filed March 18 1958
Application for plugging approved March 18 1958
Plugging commenced March 18 1958
Plugging completed March 18 1958
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4076 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	210	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy Rotary Mud to 500 ft.,
set plug and cemented with 25 sacks cement through
drill pipe. Mudded hole to 200 ft, set plug and
cemented with 1/2 sack hulls and 15 sacks cement
through drill pipe. Mudded hole to 40 ft., set plug
cemented with 1/2 sack hulls and 10 sacks cement
to bottom of cellar

3-31-58

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H 30, INC.
Address 709 Petroleum Bldg, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick
L. C. Sponenberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg
(Address) _____

SUBSCRIBED AND SWORN TO before me this 20th day of March 19 58

My commission expires Feb 13, 1960

Rose Turley
Notary Public.

PLUGGING
FILE SEC 14 T 9 R 44
BOOK PAGE 89 LINE 20

15-065-02148-0000

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS


COMPANY **Herman Geo. Kaiser, Oil Producer**

SEC. **14** T. **9** R. **21 W**
LOC. **C SW NW 4**

FARM **Kline** NO. **1**

TOTAL DEPTH **4076**
COMM. **3/8/58** COMP. **3/18/58**
SHOT OR TREATED
CONTRACTOR **H 30, Inc.**
ISSUED

COUNTY **Grabam**
KANSAS



CASING
20 10
15 8 **210**
12 6
13 5

ELEVATION **2480 OF**
2482 BF
2485 KB
PRODUCTION **D&A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Top Soil	10
Clay & Sand stks	65
Blue Shale	211
Shale	221
Shale & shells with sand stks	1240
Shale & shells	1650
Sand	1890
Shale & shells (red bed)	2132
Anhydrite	2172
Shale & shells	2207
Shale & Lime	2520
Shale & shells	2650
Shale with Lime stks	2872
Lime & Shale	3859
Kansas City Lime	4052
Lime & Shale	4076

FORMATION TOPS

Heebner 3788
Lansing 3829

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By *E. L. Spruill*

STATE OF KANSAS 0
 0 SS,
COUNTY OF SEDGWICK 0

Subscribed and sworn to before me, a notary public, in and for said County and State this 20th day of March, 1958.

Rose Turley
Notary Public

My Commission Expires February 13, 1960.

PLUGGING
SEC 14 T 9 R 24 W
BOOK PAGE 89 LINE 20