


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Graham County. Sec. 5 Twp. 9S Rge. 24W (E) (W)  
Location as "NE/CNW/SW" or footage from lines C-SE-SE-SW  
Lease Owner Sunray Mid-Continent Oil Company  
Lease Name Waite Well No. 1  
Office Address Box# 195, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 9, 19 56  
Application for plugging filed February 9, 19 56  
Application for plugging approved February 14, 19 56  
Plugging commenced February 9, 19 56  
Plugging completed February 9, 19 56  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4100 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8" | 312'   | None       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy drlg mud to 290', set bottom plug, cemented with 15 sacks from 290' to 245', filled with heavy mud to 40', set top plug cemented with 10 sacks from 40' to surface.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Halliburton Oil Well Cementing Company  
Address \_\_\_\_\_

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Norman E. Montgomery (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Norman E. Montgomery  
Box# 195, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 16 day of February, 19 56

My commission expires Dec. 24, 1956

[Signature]  
Notary Public.

2-17-56



Sunray Mid-Continent Oil Company  
Tulsa, Oklahoma

Tulsa, Oklahoma  
February 10, 1956

CONTRACTOR: Stickle Drilling Company  
Drilling Commenced: January 29, 1956  
Drilling Completed: February 2, 1956

Waite #1 SW/4 5-9S-  
24W, Graham County,  
Kansas.

DRILLERS LOG

Depth Figures Indicate Base of Formation

|                       |         |
|-----------------------|---------|
| Sand & Shale          | 315     |
| Shale & Shells        | 1485    |
| Shale & Shells & Sand | 2100    |
| Shale & Shells        | 2375    |
| Anhydrite             | 2160    |
| Shale & Lime          | 2810    |
| Lime & Shale          | 2960    |
| Shale & Lime          | 3120    |
| Lime & Shale          | 3540    |
| Shale & Lime          | 3780    |
| Lime & Shale          | 3845    |
| Lime                  | 4063    |
| Lime & Shale          | 4100 TD |

I, Frank E. Stickle hereby certify the above to be a true and complete Drillers Log of Sunray Mid-Continent Oil Company's Waite #1 SW/4 Section 5-9S-24W, Graham County, Kansas.

Frank E. Stickle  
Frank E. Stickle

Lillian T. Bonham  
Notary Public

February 13, 1956  
My Commission Expires

