


15-065-00563-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Graham County. Sec. 6 Twp. 9S Rge. 24W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE SE
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Keith "C" Well No. 1
Office Address 780 Fourth National Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 18, 1958
Application for plugging filed August 18, 1958
Application for plugging approved August 18, 1958
Plugging commenced August 18, 1958
Plugging completed August 18, 1958
Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius, Box 731, Hill City, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4045 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	8-9-58	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set No. 1 plug at 600' with 25 sacks cement; Set No. 2 plug at 215' with 15 sacks cement; Set No. 3 plug at 40' with 10 sacks cement.

RECEIVED
SEP 10 1958
COMMISSION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Raymond L. Bacon (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.
(Signature) Raymond L. Bacon V-P
780 Fourth National Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of August, 1958

My commission expires July 7, 1962
Mona L. Latier
Mona L. Latier Notary Public.

PLUGGING
FILE SEC 6 T 9 R 24 W
BOOK PAGE 127 LINE 41

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita 2, Kansas

Keith "C" No. 1
NE NE SE Sec. 6-9S-24W
Graham County, Kansas

Total Depth: 4045'

Elevation: 2480' RB
Production: D & A

Commenced: 8-9-58 Completed: 8-18-58

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 218' with 150 sacks cement.

Figures indicate bottom of formations:

Sand & Shale	218'
Shale & Shells	1645'
Shale; shells & Sand	2185'
Anhydrite	2224'
Shale & Shells	2475'
Shale; shells & Lime	2625'
Shale & Lime	3795'
Lime	4045'
Total Depth	4045'

TOPS

Anhydrite	2185'	(-295)
Heebner	3771'	(-1291)
Toronto	3796'	(-1316)
Lansing	3811'	(-1331)
Rotary Total Depth	4045'	(-1565)

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: *Wilford L. Pritchard*
Secretary

Subscribed and sworn to before me this 22nd day of August, 1958.

My Commission Expires:

July 7, 1962

RECEIVED
STATE CORPORATION COMMISSION

Mona L. Latimer
Notary Public

SEP 10 1958

DIVISION

PLUGGING	
FILE SEC	6 T 9 R24W
BOOK PAGE	127 LINE 41