


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 10 Twp. 9 Rge. 24 (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner Honaker-Davis Drlg. Co.
Lease Name Keith B Well No. 1
Office Address 2008 Lakin, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-18 1956
Application for plugging filed 5-17 1956
Application for plugging approved 5-17 1956
Plugging commenced 5-18 2:00 a.m. 1956
Plugging completed 5-18 3:30 a.m. 1956
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4070 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	229	8-5/8	229	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud to 220'. Dumped in 1/2 sack hulls. Set plug-mixed 15 sacks of cement by hand and poured through drill pipe.

Filled hole with heavy rotary mud to 40'. Dumped in 1/2 sack hulls. Set-plug-mixed 10 sacks cement by hand. Filled hole to bottom of cellar with cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Honaker-Davis Drlg. Co.
Address 2008 Lakin, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
S. C. Lingreen (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. C. Lingreen
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of May 1956

My commission expires 6-25-59
Kenneth G. Fischer, Notary Public.

5-22-56
MAY 22 1956

PLUGGING
FILE SEC 10 T 9 R 24 W
BOOK PAGE 62 LINE 44

CONSERVATION DIVISION
WICHITA, KANSAS

DRILLERS LOG

Keith B No. 1
 Loc: NE NE SW
 Sec: 10-9-24
 Graham County, Kansas
 Company: Honaker-Davis Drlg. Co., et al
 Contractor: Honaker-Davis Drlg. Co.

Comm: 5-9-56
 Comp: 5-18-56
 Rotary Total Depth: 4070
 Casing: 8-5/8" at 230'
 D & A

0	50	Top soil & Clay	
50	110	Sand & Gravel	
110	155	Post Rock & Sand	8-5/8" casing cemented at
155	750	Blue Shale	231' with 175 sacks cement
750	930	Sand	and 4 sacks calcium chloride
930	1450	Shale	
1450	2150	Red Bed & Shale	
2150	2195	Anhydrite	
2195	2450	Shale & Shells	
2450	3885	Lime & Shale	
3885	3966	Lime	
3966	4070	Lime & Shale	
4070		Total Rotary Depth	

I certify that this is the true and correct copy of
 the above log to the best of my knowledge.

H. C. Davis
 H. C. Davis

Subscribed and sworn to before me this 21st day of
 May, 1956.

Kenneth C. Fischer
 Kenneth C. Fischer, Notary Public

My commission expires; 6-25-59

