


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 11 Twp. 9S Rge. (E) 24(W)  
Location as "NE/CNW%SW%" or footage from lines C NE NE  
Lease Owner Imperial Oil Company  
Lease Name Bell Well No. 1  
Office Address 780 Fourth Nat'l Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 10-30-61 19  
Application for plugging filed 10-30-61 19  
Application for plugging approved 10-30-61 19  
Plugging commenced 10-30-61 19  
Plugging completed 10-30-61 19  
Reason for abandonment of well or producing formation No commercial quantities of oil found.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4054 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		Surface	Pipe	7"	222'	Not pulled

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set first plug at 550' with 15 sacks cement;  
second plug at 200' with 15 sacks cement;  
set top plug at 40' with 10 sacks cement,

11-13-61



(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Chemical & Technical Services, Inc.  
Address Box 728, Hill City, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
W. A. Sladek (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William A. Sladek  
780 Fourth National Bldg., Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of November, 19 61  
Bette J. Behymer  
Bette J. Behymer Notary Public.

My commission expires July 27, 1964



15-065-00668-0000

RECEIVED  
STATE OF KANSAS  
COMMISSION DIVISION  
WICHITA, KANSAS

DRILLER'S LOG

Imperial Oil Company  
780 Fourth National Building  
Wichita 2, Kansas

Bell No. 1  
C NE NE Sec. 11-9S-24W  
Graham County, Kansas

Total Depth: 4054

Elevation: 2469 K.B.  
Production: Dry

Commenced: 10-23-61 Completed: 10-30-61

Contractor: Chem-Tech  
Box 728  
Hill City, Kansas

Casing Record: Set 7" surface pipe at 220' with 90 sacks cement.

Figures indicate bottom of formations:

TOPS

Shale & Sand	221'	Heebner	3785 (-1316)
Shale	925'	Toronto	3810 (-1341)
Sand & Shale	1600'	Lansing	3825 (-1356)
Red Bed	1800'	Base Kansas City	4045 (-1576)
Shale & Red Bed	2130'	Total Depth	4054 (-1585)
Anhydrite	2174'		
Red Bed & Shale	2285'		
Shale & Shells	2610'		
Shale & Lime	2820'		
Lime & Shale	3770'		
Lime	4054'		
Rotary Total Depth	4054'		

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

By Raymond L. Bacon  
Raymond L. Bacon

Subscribed and sworn to before me this 10th day of November, 1961.

My Commission Expires:

July 27, 1964

Bette J. Behymer  
Bette J. Behymer, Notary Public