

15-065-02876-0000 A. Reed  
 10. COPY


STATE OF KANSAS  
 STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit  
 Mail or Deliver Report to  
 Conservation Division  
 State Corporation Comm.  
 245 North Water  
 Wichita, KS 67202

Graham County, Sec. 33 Twp. 9 Rge. 24 NW  
 Location as "NE/CNW/SW" or footage from lines  
 NE NE NW

Lease Owner George A. Reed  
 Lease Name Critchfield Well No. 1  
 Office Address 100 N. Broadway, Wichita, Kansas 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole)



Oil  
 Date Well completed October 7 1957  
 Application for plugging filed June 17 1983  
 Application for plugging approved July 1983  
 Plugging commenced August 18 1983  
 Plugging completed August 18 1983  
 Reason for abandonment of well or producing formation  
Depleted

If a producing well is abandoned, date of last production  
June 1983

Was permission obtained from the Conservation Division or  
 its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow  
 Producing formation Lansing - KC Depth to top          Bottom          Total Depth of Well 4110  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	Cement	0	396'	8 5/8	396'	None
Long-String	Cement	0	4110'	5 1/2	4106'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet for each plug set. Had Sun Cementing mix 2 sacks of hulls and 350 sacks of 50/50 poz, 6% gel, 3% c.c. Pumped it down the casing.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pfeifer-Sharpe, Inc.

STATE OF Kansas COUNTY OF Graham, ss.  
Ron Sulzman (employee of ~~XXXXXXX~~) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
P. O. Box 386, Hill City, Kansas 67642  
 (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of September, 19 83

My commission expires May 12, 1986

[Signature]  
 Notary Public.  
 STATE CORPORATION COMMISSION  
 9-21-83  
 SEP 21 1983  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

1 15-065-02876-0000

BUS: 316-262-3193

RES: 316-686-1862

**GEORGE A. REED**  
*Oil and Gas Producer*  
FOURTH FINANCIAL CENTER, SUITE 535  
100 NORTH BROADWAY  
WICHITA, KANSAS 67202

June 10, 1983

Pfeifer Well Service, Inc.  
P. O. Box 386  
Hill City, Kansas 67642

Re: George A. Reed  
Critchfield #1  
NE NE NW Sec. 33-9S-24W  
Graham County, Kansas

Gentlemen:

I believe this information is what you will need to secure a permit to plug the captioned well:

ELEVATION	2524 Derrick Floor
CASING	8-5/8" (22.7#) Cemented @ 396 w/225 sacks 5-1/2" (14#) Cemented at 4106 w/200 sacks
FORMATION TOPS:	ANHYDRITE 2175-2210 HEEBNER SHALE 3822 TORONTO 3844 LANSING 3856 ROTARY TD 4110
PERFORATIONS:	3858-3866 with 48 holes 4005-4009 with 16 holes 4026-4030 with 16 holes 4038-4036 with 48 holes

This well was drilled by Skelly Oil Company. Spud date was September 3, 1957, and the well was put on pump October 7, 1957.

I purchased this well from Skelly with effective date being December 1, 1970.


The Dakota Sand, from 1740' to 1930' broke in late in September, 1977, and on October 12, 1977, the leak in the casing at 1735' was squeezed by Halliburton with 300 sacks of 60-40 Posmix, no gel, containing 1% calcium chloride.

My operator's license number is #6639.

Field name is questionable. In one place I find it to be Hoeting and in another I find it to be Glendale.

Should you need additional information for a permit to plug, please let me know and I will furnish it at once.

Very truly yours,



George A. Reed

GAR:cj

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 15 1983  
CONSERVATION DIVISION  
Wichita, Kansas