

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-21774-0006

LEASE NAME Critchfield "B"

WELL NUMBER 2

SPOT LOCATION SW NW SW

SEC. 33 TWP. 9S RGE. 24W (E) or (W)

COUNTY Graha,

Date Well Completed 5/83

Plugging Commenced _____

Plugging Completed _____

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Murfin Drilling Company

ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202

PHONE # () 267-3241 OPERATORS LICENSE NO. 6033

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #6-Hays

Is ACO-1 filled? no If not, is well log attached? no

Producing formation LKC Depth to top 4046' bottom 4066' T.D. 4155'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	350'	-
				4 1/2"	4151'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Connected to 4 1/2" csg. Pumped 190 sx. Econolite cement w/5 sx. hulls. Max 800 psig, SIP 150 psig. Connected to 8 5/8" & 4 1/2" annulus. Pumped 60 sx. Econolite cement w/1 sx hulls. Max 350 psig, SIP 150 psig. Filled to surface w/.5 yds Redi-mix. Volume of cement pumped down annulus is = to 916'. Volume of cement pumped down 4 1/2" csg. is = to 7600'.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. 6033
Address Wichita, KS

STATE OF Kansas COUNTY OF Sedgwick, ss.

Larry M. Jack, Eastern Division, Prod. Mgr. (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

JAN 30 1987
1-30-87
CONSERVATION DIVISION
Wichita, Kansas

(Signature) By: Larry M Jack

(Address) Wichita, KS

 KERRAN REDINGTON
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 2-6-90

SUBSCRIBED AND SWORN TO before me this 29 day of Jan., 19 87

Kerran Redington
Notary Public

My Commission expires: 2/6/90