

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Graham County. Sec. 33 Twp. 9S Rge. 24W (E) (W)

Location as "NE/CNW/SW" or footage from lines C W/2 NW NE

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name Kohart "B" Well No. 1

Office Address 780 Fourth National Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed January 17 19 58

Application for plugging filed April 28 19 59

Application for plugging approved April 30 19 59


Plugging commenced June 6 19 59

Plugging completed June 10 19 59

Reason for abandonment of well or producing formation Commercial quantities of oil depleted.

If a producing well is abandoned, date of last production June 5 19 59

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricius

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4099 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	218'	218'
				8-5/8"		
				5-1/2"	4099'	4099'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded hole back to 4024', mixed and run 3 sacks cement with dump bailer. Cleaned out cellar. Took tension on pipe, worked tension 20' shot and worked pipe @ 3400' 3300' 3200' casing working free. Worked pipe free and pulled 60 jts. Pulled 48 jts. pipe. Tore down, bailed fluid and filled hole with mud to 215' set 10' rock bridge. Mixed and run 25 sacks cement @ 205' with dump bailer. Filled hole with mud to 40' set 10' rock bridge with 10 sacks cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.

Address P. O. Box 364, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Raymond L. Bacon (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.


(Signature) By: Raymond L. Bacon V-P

780 Fourth National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of June, 1959

My commission expires July 7, 1962

Mona L. Latier
Mona L. Latier Notary Public.



DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita 2, Kansas

Kohart "B" No. 1
C/W¹/₂ NW NE Sec. 33-9-24W
Graham County, Kansas

Total Depth: 4099'

Elevation: 2529' RB
Production: 101 BOPD / 40% Wtr.

Commenced: 1-1-58 Completed: 1-17-58

Contractor: Imperial Oil of Kansas, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 218' with 150 sacks cement.

Figures indicate bottom of formations:

Surface Clay and Sand	40'		<u>TOPS</u>	
Sand & Shale	1590'	Anhydrite	2175'	(/ 354)
Dakota Sand	1830'	Heebner	3832'	(-1303)
Shale & Red Bed	2175'	Toronto	3856'	(-1327)
Anhydrite	2212'	Lansing	3868'	(-1339)
Shells & Shale	2520'	Rotary Total Depth	4099'	(-1570)
Shale & Lime	3880'			
Lime	4099'			
Total Depth	4099'			

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: Ray L. Bacon
Vice-President

Subscribed and sworn to before me this 17th day of January, 1958.

My Commission Expires:

December 19, 1960

RECEIVED
STATE COMMISSION

Luella M. Duncan
Notary Public

AUG 14 1959

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 33 T. 9 R. 24W
BOOK PAGE 34 LINE 17