

15-065-02142-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

GRAHAM County. Sec. 1 Twp. 9 Rge. 25 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE  
Lease Owner EMPIRE DRILLING COMPANY  
Lease Name CLARK "B" Well No. 1  
Office Address 400 BROWN BLDG., WICHITA 2, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed JULY 11 1956  
Application for plugging filed JULY 11 - VERBAL 1956  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced JULY 11 1956  
Plugging completed JULY 11 1956  
Reason for abandonment of well or producing formation \_\_\_\_\_  
DRY HOLE

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MILTON GALYARDT  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3995 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	195'	CEMENTED

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

BOTTOM PLUG SET AT 155 FT. WITH 15 SACKS CEMENT  
TOP PLUG SET AT 40 FT. WITH 10 SACKS CEMENT.

RECEIVED  
STATE CORPORATION COMMISSION  
7-24-56  
JUL 24 1956  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor EMPIRE DRILLING COMPANY  
Address 400 BROWN BLDG., WICHITA 2, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
I, DAN J. KORNFELD (~~EMPLOYEE OF XXXXX~~) operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
DAN J. KORNFELD  
400 BROWN BUILDING, WICHITA 2, KANSAS  
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of JULY, 1956

[Signature]  
Notary Public.

My Commission Expires Oct. 21, 1958

PLUGGING  
FILE SEC. 1 T. 9 R. 25W  
BOOK PAGE 80 LINE 3

LOG

COMPANY: EMPIRE DRILLING COMPANY

CONTRACTOR: EMPIRE DRILLING COMPANY

FARM: CLARK "B" No. 1

LOCATION: NE NE NE OF SEC. 1-9-25, GRAHAM COUNTY, KANSAS

COMMENCED: JULY 3, 1956

COMPLETED: JULY 11, 1956

ELEVATION: 2475 K.B.

-----

0	TO	195	SHALE AND SAND	TOPS:		
195	TO	430	SHALE AND SHELLS			
430	TO	1630	SHALE AND SAND	HEEBNER	3771	-1296
1630	TO	2115	SHALE, SAND AND SHELLS	TORONTO	3794	-1319
2115	TO	2175	SHALE AND SHELLS	LANSING KANSAS CITY	3812	-1337
2175	TO	2210	ANHYDRITE			
2210	TO	3220	SHALE AND SHELLS			
3220	TO	3293	SHALE AND LIME			
3293	TO	3440	SHALE AND SHELLS			
3440	TO	3560	SHALE AND LIME			
3560	TO	3680	LIME AND SHALE			
3680	TO	3776	SHALE AND LIME			
3776	TO	3995	LIME			
3995			R.T.D.			

DRY AND ABANDONED


CASING RECORD: RAN 195 FT. OF 8 5/8" AND CEMENTED WITH 115 SACKS CEMENT.

D.S.T. NO. 1 3958-3975 TOOL OPEN ONE HOUR. WEAK BLOW FOR 45 MINUTES. INTERMITTENT WEAK BLOW FOR 15 MINUTES. RECOVERED 30 FT. OF OIL CUT MUD. 30 MINUTES SHUT-IN BOTTOM HOLE PRESSURE - 210 LBS.

D.S.T. NO. 2 3974-3995 TOOL OPEN 45 MINUTES. WEAK BLOW FOR 3 MINUTES. RECOVERED 6 FT. OF MUD WITH SPOTS OF OIL. 30 MINUTES SHUT-IN BOTTOM HOLE PRESSURE - 180 LBS.

-----

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE CLARK "B" No. 1, NE NE NE OF SEC. 1-9-25, GRAHAM COUNTY, KANSAS, AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

  
 DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 23rd DAY OF JULY, 1956.

  
 NOTARY PUBLIC

MY COMMISSION EXPIRES My Commission Expires Oct. 21, 1958

PLUGGING  
 FILE SEC. 1 T. 9 R. 25W  
 BOOK PAGE 80 LINE 3