


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Graham County. Sec. 1 Twp. 9S Rge. 25 (~~XXXX~~ W)
Location as "NE/CNW%SW%" or footage from lines C S/2 SE SW

Lease Owner Empire Drilling Company & Time Petroleum Company

Lease Name Everette Keith Well No. 1

Office Address 650 4th Natl. Bank Bldg. & 815 Union Natl. Bldg. Wichita,

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole Kansas

Date well completed March 9 19 65

Application for plugging filed March 9 19 65

Application for plugging approved March 9 19 65

Plugging commenced March 9 19 65

Plugging completed March 9 19 65

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Morland, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3918 RTD Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface - Shale	0	203	8 5/8"	172'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set at 540' with 20 sacks cement.
Plug set at 180' with 20 sacks cement.
Plug set at 40' with 1 sack hulls & 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
3-15-65
MAR 15 1965
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company

Address 650 Fourth National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Theodore Gore

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Theodore Gore
Theodore Gore
650 4th Natl. Bank Bldg. Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of March, 19 65

My commission expires September 14, 1968

Sandra Kay Peer
Sandra Kay Peer
Notary Public.

LOG

COMPANY: Empire Drilling Company and Time Petroleum Company
 CONTRACTOR: Empire Drilling Company
 FARM: Everette Keith #1
 LOCATION: C S/2 SE SW Section 1-9S-25W, Graham County, Kansas
 COMMENCED: March 1, 1965 ELEVATION: 2524 KB
 COMPLETED: March 9, 1965 POTENTIAL: D & A

0	to	203	Surface - Shale
203	to	1063	Shale
1063	to	1388	Sandy Shale
1388	to	1953	Shale & Sand
1953	to	2219	Shale - Red Bed
2219	to	2253	Anhydrite
2253	to	2393	Shale & Lime
2393	to	2616	Shale & Shells
2616	to	3180	Shale - Lime
3180	to	3298	Lime
3298	to	3413	Lime & Shale
3413	to	3534	Lime
3534	to	3753	Lime & Shale
3753	to	3918	Lime
3918			Rotary Total Depth

SET: 172' of 8 5/8" with 85 sacks cement.

SAMPLE LOG TOPS:

Anhydrite	2219	+305
Queen Hill	3702	-1178
Heebner	3814	-1290
Toronto	3839	-1315
Lansing	3854	-1330
Rotary Total Depth	3918	

RECEIVED
STATE CORPORATION COMMISSION

MAR 15 1965

CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATION

I, Theodore Gore, do hereby certify that the above and foregoing is a true and correct copy of the log on the Everette Keith #1, C S/2 SE SW Section 1-9S-25W, Graham County, Kansas, as reflected by the files of Empire Drilling Company.

Theodore Gore
Theodore Gore

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 12th day of March, 1965.

Sandra Kay Peer
Sandra Kay Peer, Notary Public

My commission expires September 14, 1968