

API NUMBER 15-065-22,289-0000

LEASE NAME Bittel

WELL NUMBER 1

990 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 5 TWP. 9 RGE. 25 (W) or (W)

COUNTY Graham

Date Well Completed 2-27-86

Plugging Commenced 2-27-86

Plugging Completed 2-27-86

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Sage Drilling Co., Inc.

ADDRESS 202 S. St. Francis, Wichita, KS 67202

PHONE#(316) 263-6139 OPERATORS LICENSE NO. 5421

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, KS 2-26-86 8:45 am

Is ACO-1 filed? yes If not, is well log attached? well logs are attached

Producing Formation none Depth to Top \_\_\_\_\_ Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing	water	3852	99	8-5/8"	318	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
4135-2300': 9.2 ppg mud; 2300-2210: 25 sx. 60-40 pozmix, 4% gel (1 sk Flocele throughout all cmt)  
2210-1350': 9.2 ppg mud; 1350-985': 100 sx. 60-40 pozmix, 4% gel; 985-340': 9.2 ppg mud; 340-  
200': 40 sx. 60-40 pozmix, 4% gel; 200-40': 9.2 ppg mud; Wooden plug @ 40'; 40-0': 10 sx. 60-  
40 pozmix, 4% gel; 15 sx. 60-40 pozmix, 4% gel in rat hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sage Drilling Co., Inc. License No. 5421

Address 202 S. St. Francis, Wichita, KS 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


Charles Casey Coats (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Charles Casey Coats  
 Charles Casey Coats  
 (Address) 202 S. St. Francis, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 28 day of February, 1986

Sandra Kay Hiner  
 Sandra Kay Hiner Notary Public

My Commission Expires: 6-5-88



STATE CORPORATION COMMISSION  
 3-3-86  
 MAR 3 1986

Form CP-4  
 Revised 08-84