

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-065-01631-0001

API NUMBER E-1962

LEASE NAME Dreiling

WELL NUMBER #1

3630 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 5 TWP. 9 RGE. 25 (E) or (W)

COUNTY Graham

Date Well Completed 02-25-62

Plugging Commenced 01-29-98

Plugging Completed 01-29-98

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Great Plains Petroleum, Inc.

ADDRESS 221 Circle Drive

PHONE# (316) 685-8800 OPERATORS LICENSE NO. 30163

Character of Well SWD EOR
2TKCC
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-01-97 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, is well log attached? Yes

Producing Formation LKC Depth to Top 3828 Bottom 3844 T.O. 4046

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
 KANSAS CORPORATION COMMISSION

8-12-98

Formation	Content	From	To	Size	Put in	Pulled out
Fresh Water	150 sx	0	206	8-5/8"	206'	0
LKC	125 SX			5-1/2"	4046'	0
Dakota	550 SX	0	2230	5-1/2"	4046'	0

AUG 22 1998

CONSERVATION DIVISION
 WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Squeeze down 5-1/2 csg. with 50 sx cement and 300# Hulls, 14 sx gel, 150 sx cement. Pressure to 100 psi holding. 8-5/8" csg. Full of cement. Total 200 sx. Cement blend 60-40 with 10% gel.

Name of Plugging Contractor Chase Well Service License No. 6123

Address P.O. Box 355 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Great Plains Petroleum, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.

David B. Pauly, Jr. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 100 S. Main, Suite 415

SUBSCRIBED AND SWORN TO before me this 21 day of May, 1998



Commission Expires: 2/22/99 Notary Public