


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Graham County, Sec. 5 Twp. 9S Rge. 25 (E) W (W)

Location as "NE/CNW/SE" or footage from lines NW NE SE

Lease Owner Glickman Oil Company

Lease Name Dreiling

Well No. 3

Office Address 702 S. St. Francis Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 7, 19 64

Application for plugging filed January 7, 19 64

Application for plugging approved January 7, 19 64

Plugging commenced January 7, 19 64

Plugging completed January 7, 19 64

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Bill Nichols, Morland, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4010 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	171	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

~~XXXXXX~~ - Set first plug @ 550' - 20 sks cement
Heavy mud to 160' - 20 sks cement
Heavy mud to 40' - 1/2 sk Hulls - 8 sks cement
Hole plugged @ 8:00 A.M.

RECEIVED
STATE CORPORATION COMMISSION
1-23-64
JAN 23 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glickman Oil Company

Address P. O. Box 3104 Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Milton Glickman

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Milton Glickman

(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of January, 19 64

My commission expires November 19, 1967

Lorella Schauf

Notary Public.

GLICKMAN OIL COMPANY

P. O. Box 3108

Wichita, Kansas

DRILLERS WELL LOG

Company: Glickman Oil Company

Location: NW NE SE 5-9S-25W
Graham County, Kansas

Farm: Dreiling Well No. 3

Commenced: December 30, 1963

Elevation: 2486 KB

Completed: January 8, 1964

Total Depth: 4010 RTD ^{RT}_{KCC}

Casing: 8 5/8" @171'

Production: D & A

Geologist: Max S. Houston

Figures Indicate Bottom of Formations

345	Shale		
2040	Shale		
2174	Red Bed Shale		
2209	Anhydrite	TOPS	
2220	Shale		
2460	Shale and Shells	Anhydrite	2174
2615	Shale	Heebner	3732
2840	Shale with Lime Streaks	Toronto	3751
3030	Shale with Lime	Lansing	3769
3173	Shale with Lime Streaks	Base Kansas City	3999
3825	Shale and Lime		
4006	Lime and Shale		
4010	Shale		

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1964

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss:

I, Milton Glickman, of the Glickman Oil Company, upon oath state that the above and foregoing is a true and correct copy of the log of the Dreiling # 3.

Milton Glickman
Milton Glickman

Subscribed and sworn to before me this 17th day of January, 1964.

Lorella Schauf
Lorella Schauf

Notary Public

My Commission Expires: November 19, 1967