

STATE OF KANSAS
STATE CORPORATION COMMISSION
208 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-227730000

LEASE NAME Dreiling

WELL NUMBER 3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3120 Ft. from S Section Line

330 Ft. from E Section Line

LEASE OPERATOR Great Plains Petroleum, Inc.

SEC. 5 TWP. 9 RGE. 25 (X or W)

ADDRESS 1902 E. Waterman, Wichita, KS 67211

COUNTY Graham

PHONE# (316) 264-3624 OPERATORS LICENSE NO. 30163

Date Well Completed 8/18/96

Character of Well D&A

Plugging Commenced 8/18/96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8/18/96

The plugging proposal was approved on 8/18/96 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? yes ~~no~~ If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4360 Ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation Surface	Content	From 248'	To 0'	Size 8-5/8"	Put in 248'	Pulled out None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged with 200 sacks 60/40 Pozmix, 6% gel, 1/4# floseal per sack as follows: 25 sx @ 2250', 100 sx @ 1350', 40 sx @ 300', 10 sx @ 40', 15 sx rathole, 10 sx mousehole. P.D. @ 12:00 pm 8/18/96.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard JV, Inc. License No. 4858
P. O. Box 1009, McPherson, KS 67460 KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Great Plains Petroleum, Inc. FEB 27 1997


STATE OF Kansas COUNTY OF Sedgewick, ss. 2-27-97

Rad A. Phares, President (Employee of Operator) or (Notary Public) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Rad A. Phares

(Address) 221 Circle Drive, Wichita, KS 67218

Subscribed and sworn to before me this 26th day of February, 19 97



Melaina J. Volz Notary Public

My Commission Expires: 07-15-00

MALLARD JV, Inc.
DRILLING CONTRACTORSP. O. Box 1009
McPHERSON, KS 67460

316-241-4640

Drillers LogOPERATOR: **Great Plains Petroleum, Inc.**
1902 E. Waterman
Wichita, KS 67211WELL: **Dreiling #3**

API #: 15-065-227730000

COMMENCED: August 10, 1996

LOCATION: 150' N of SE SE NE
3120' FSL, 330' FEL
Section 5, Township 9 S, Range 25 W
Graham County, Kansas

COMPLETED: August 18, 1996

TOTAL DEPTH: 4360'

ELEVATION: 2538' GL, 2543' KB

STATUS: Dry and Abandoned - Mississippian Formation

SPUD: 10:10 pm 8/10/96

SIZE HOLE DRILLED: 12-1/4" x 250'

SURFACE CASING SIZE: 8-5/8" x 28# x 241.46' (7 jts.)

SET AT: 247.9'

CEMENT: 165 sacks 60/40 Pozmix, 2% gel, 3% cc

SIZE HOLE DRILLED: 7-7/8" x 4360' RTD

PLUGGED HOLE WITH: 200 sacks 60/40 Pozmix, 6% gel, 1/4# floseal per sack as follows:

25 sx @ 2250'

100 sx @ 1350'

40 sx @ 300'

10 sx @ 40'

15 sx rathole,

10 sx mousehole

P. D.: 12:00 pm 8/18/96

DRILL STEM TESTS: 3

ELECTRIC LOG: Yes

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 27 1997

CONSERVATION DIVISION
WICHITA, KS