


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 17 Twp. 9S Rge. 25W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW SW NW  
Lease Owner Empire Drilling Company  
Lease Name Gay Rush Well No. 1  
Office Address 650 Fourth Nat'l Bk. Bldg., Wichita, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 6-23-67 19  
Application for plugging filed 6-23-67 19  
Application for plugging approved 6-23-67 19  
Plugging commenced 6-23-67 19  
Plugging completed 6-23-67 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4097 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	208'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud to 540', set plug with 20 sks. cement  
Filled hole with mud to 220', set plug with 20 sks. cement  
Filled hole to 40' with mud, set plug bridge with 1/2 sk. hulls & 10 sks. cement to cellar bottom

RECEIVED  
STATE CORPORATION COMMISSION  
6-27-67  
JUN 27 1967  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
~~XXXXXXXXXX~~ Doug Boyd (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Doug Boyd  
Box 486, Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of June, 1967

My commission expires April 1, 1971  
Ulanda Nichols Notary Public.

DRILLER'S LOG

COMPANY: Empire Drilling Company  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: GAY RUSH #1  
 LOCATION: SW SW NW SEC. 17-9S-25W  
 GRAHAM COUNTY, KANSAS  
 COMMENCED: 6-17-67  
 COMPLETED: 6-23-67

0	150	Clay, Sand
150	208	Blue Shale
208	1830	Shale
1830	2295	Redbed
2295	2325	Anhydrite
2325	2425	Shale, Shells
2425	2760	Lime, Shale, Pyrite
2760	3580	Lime, Shale
3580	4097	Lime
	<u>4097</u>	<u>RTD - D. &amp; A.</u>

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 27 1967  
 CONSERVATION DIVISION  
 Wichita, Kansas

8 5/8" 8 rd. 24# used surface casing set @ 208' cemented with 160 sacks Common, 2% cc

I, Doug Boyd, do hereby certify that the above and foregoing is a true and correct copy of the log of the Gay Rush #1 Well, located SW SW NW of Section 17, Township 9 South, Range 25 West, Graham County, Kansas, as reflected by the records of Leben Drilling, Inc.

*Doug Boyd*

Doug Boyd

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON )

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 26th day of June, 1967.

*Ulanda Nichols*

Ulanda Nichols

My Commission Expires:  
 April 1, 1971