

15-065-30188-0002

6 030380

API NUMBER 15-

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SESESW, SEC. 23, T. 9 S, R 24 WE
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5145

Lease Name Nicholson Well # A-1 SWD

Operator Name: Drilling oil Inc.

County Graham 65.00

Address Box 1000

Well Total Depth 2000 feet

Victoria Kansas

Conductor Pipe: Size _____ feet

67671

Surface Casing: Size 8 5/8 feet 215 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Drilling oil Inc. License Number 730

Address Box 1000 Victoria Kansas 67671

Company to plug at: Hour: AM Day: 15 Month: 2 Year: 19 85

Plugging proposal received from Bill Oraper

(company name) Drilling oil Inc. (phone) _____

were: Order 250 sq 50/50 pox 62 gel 3% cc - 4 sq hulls.

8 5/8 set @ 215 with 150 sq. 4 1/2 set @ 2000 sq N.A. (well was converted with bottom plugged with 5 sq Hulls 30 sq gel and 100 sq Cement to 2000' with 250# pressure and shut in of 75# Perf. at 1750' to 1850') allied cement company

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:30 AM Day: 15 Month: 2 Year: 19 85

ACTUAL PLUGGING REPORT Pumped down 4 1/2 with 140 sq Cem. mix

Pressure to 300# shut in 150# Pumped down annulus 110

sq cement and 4 sq hulls. Pressure to 300# shut in 0# as

leak occurred at top of 8 5/8 in cellar.

STATE CORPORATION COMMISSION
2-23-85
FEB 25 1985

Remarks: _____

If additional description is necessary, use BACK of this form.)

DATE 2-26-85 (418 / 414 not) observe this plugging.

IV. NO. 7133

Signed Carl Goodrow 2-22-85
(TECHNICIAN)