

6 031463

8 12-13  
API NUMBER 15-065-30172-0001 <sup>1066</sup> *new R*

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW SE SW SEC. 23', T 9 S, R 24 W/E  
990 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5145

Lease Name Nickelson A Well # A 2

Operator: Dreiling Oil Inc.

County Graham 132.27

Name & Address Box 1000

Well Total Depth 4070 feet

Victoria, Ks. 67671

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 217

Abandoned Oil Well Gas Well Input Well SWD Well xx D&A

Other well as hereinafter indicated Docket D-23,307

Plugging Contractor Allied Cement Co. License Number

Address Russell, Ks.

Company to plug at: Hour: PM Day: 13 Month: Dec. Year: 19 90

Plugging proposal received from Ivan

(company name) Dreiling (phone)

were: 8 5/8 set at 217 cwc 150 sks. 4 1/2 set at 4069 w/150 sks. PBDT 3800.

Perf at 1935 and sq w/375 sks to surf. Perf 1702-1802.

Order workstring and 150 sks 65/35 poz 8% gel Allied Cement Co. Company water trucks.

Stamp: RECEIVED  
JAN 14 1991  
CONSERVATION DIVISION  
WICHITA, KANSAS

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part None

Operations Completed: Hour: 12:00 PM Day: 13 Month: Dec. Year: 19 90

ACTUAL PLUGGING REPORT Ran tubing to 2100 circ cement to surf and sq

4 1/2 casing w/total of 110 sks cement blend to max psi 1000 lbs. Close in psi 300 lbs.

8 5/8 annulus took 15 sks to max psi 500 lbs. Close in psi 500 lbs. Plug complete.

Remarks:

INVOICED

(If additional description is necessary, use BACK of this form.)

(did / did not) observe this plugging.

DATE 2-7-91

INV. NO. 30520

*J.S.*

Signed Carl Goodrow (TECHNICIAN)  
Carl Goodrow