

15-065-00579-0001

4-041546

D-09,090

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 11-18-58

SE SE SW /4 SEC. 24 , 09 S, 24 W  
2970 feet from S section line  
2970 feet from E section line

Operator license# 6588

Lease Drury well # B 1

Operator: Woodman Iannitti Oil Co.

County Graham 30.65

Address: P.O. Box 308  
Great Bend, Kansas  
67530-0308

Well total depth 4020 feet PB 1900'  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 169 feet  
w/125 sxs.

Aband. oil well \_\_, Gas well \_\_, Input well \_\_, SWD X, D & A \_\_

Plugging contractor: Allied Cementing License# \_\_\_\_\_

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 29 Month: November Year: 93

Plugging proposal received from: Dick Iannitti

Company: Woodman Iannitti Oil Company Phone: \_\_\_\_\_

Were: 5 1/2" casing set @ 4015' w/75 sxs. cement. Perf. @ 1730'-1805'.  
5 1/2" casing squeezed from anhy. to surface July 16, 1964.  
4 1/2" liner set @ 1630' circulated cement to surface.  
Ordered 100 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 100# hulls.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[ X ], Part[ ], None[ ]

Completed: Hour: 10:20A.M., Day: 29, Month: November, Year: 93

Actual plugging report: Hooked-up to 4 1/2" casing. Pumped in 100 sxs. cement with 1/4# F.C. Max. 1000#. S.I.P. 1000#.

RECEIVED  
STATE CORPORATION COMMISSION  
12-21-93  
DEC 21 1993

Remarks:  
Condition of casing(in hole): GOOD X BAD \_\_\_\_\_ Anhy. plug: YES X NO \_\_\_\_\_  
Bottom plug(in place): YES X, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING X. Elevation: \_\_\_\_\_ GL

CONSERVATION DIVISION  
WICHITA, KANSAS

I did X did not [ ] observe the plugging.

Dennis L. Hamel

DATE DEC 28 1993

FD

(agent)

Form CP-2/3

INV. NO. 39552

11-29