

15-065-01617-0000

4-041547

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 12-29-59

C NE SW /4 SEC. 24 , 09 S, 24 W
1980 feet from S section line
3300 feet from E section line

Operator license# 6588 Lease Drury "B" well # 1

Operator: Woodman Iannitti Oil Co. County Graham

Address: P.O. Box 308
Great Bend, Kansas
67530-0308 Well total depth 3980 feet ^{29.35}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 149 feet
w/130 sxs.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:30A.M. Day: 29 Month: November Year: 93

Plugging proposal received from: Dick Iannitti

Company: Woodman Iannitti Oil Company Phone:

Were: 5 1/2" casing set @ 3971' w/130 sxs. cement. Perf. @ 3831'-3918'.
Anhy. @ 2075' - Dakota @ 950' - Pulled October 10, 1993.
Ordered 275 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls
plus 10 sxs. gel.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:45P.M., Day: 29, Month: November, Year: 93

Actual plugging report: Hooked-up to 5 1/2" casing. Squeezed in 50 sxs.
cement with 200# hulls, followed with 10 sxs. gel followed with 175 sxs.
cement with 200# hulls. Max. 1000#. S.I.P. 800#.
8 5/8" - Pumped down 50 sxs. cement with 100# hulls. Max. 1000#.
S.I.P. 800#.

Remarks: Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X , CALC , NO Dakota plug: YES X , NO
Plugged through TUBING , CASING X . Elevation:

I did[X]/ did not[] observe the plugging.

Dennis L. Hamel
(agent)

RECEIVED
STATE CORPORATION COMMISSION
12-21-93
CONSERVATION DIVISION
Wichita, Kansas

DATE DEC 28 1993

W.C. NO. 39553

11-29