

15-065-01618-0000

4-041548

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 6-16-60

C E2 SW /4 SEC. 24 , 09 S, 24 W
1980 feet from S section line
3300 feet from E section line

Operator license# 6588 Lease Drury "B" well # 2

Operator: Woodman Iannitti Oil Co. County Graham

Address: P.O. Box 308 Well total depth 3985 feet ^{129.51}
Great Bend, Kansas Conductor Pipe: 0 inch @ 0 feet
67530-0308 Surface pipe 8 5/8 Inch @ 152 feet
w/130 sxs.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:30A.M. Day: 29 Month: November Year: 93

Plugging proposal received from: Dick Iannitti

Company: Woodman Iannitti Oil Company Phone:

Were: 5 1/2" casing set @ 3975' w/75 sxs. cement. Perf. @ 3795'-3921'.
Anhy. @ 2075' - Dakota @ 950' - T.O.F. @ 1800' - Tubing pulled 10-10-93.
Ordered 275 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls
plus 10 sxs. gel.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:15P.M., Day: 29, Month: November, Year: 93

Actual plugging report: Hooked-up to 5 1/2" casing. Pumped in 50 sxs.
cement with 200# hulls, followed with 10 sxs. gel followed with 175 sxs.
cement with 200# hulls. Max. 1000#. S.I.P. 800#.
Hooked-up to 8 5/8". Pumped in 50 sxs. cement with 100# hulls.
Max. 1000#. S.I.P. 800#.

RECEIVED
STATE CORPORATION COMMISSION
12-21-93
3021 1993

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did X] did not] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED
DATE DEC 28 1993
INV. NO. 39551
11-29