

6050171

API NUMBER 15-06522137-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE New Sw, SEC. 27, T. 9 S, R 24 W/8

1650 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5430

Lease Name Eye Moor Well # 1

Operator: Energy Three Inc.

County Graham 132.93

Name & Address P.O. Box 1505

Well Total Depth 4090 feet

Great Bend Kas.

Conductor Pipe: Size \_\_\_\_\_ feet

67530

Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Big Three Drilling Co. License Number \_\_\_\_\_

Address P.O. Box 52 Graham Kas 67640

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Stan Lovelady

(company name) Big Three Drilling (phone) \_\_\_\_\_

were: Order 205 sac 50/50 Mudmix 670 Pkg Gel - 3% @ - 1 sk Flocc - 878 Pkg 1 sac shells.

Let Pitts circulate hole with heavy mud - heavy mud between all plugs. No fluid loss. Set 1st Plug @ 2170' and 25 sac - 2nd Plug @ 1340' and 110 sac 1 sac flocc oil 3rd Plug 280' and 40 sac - 4th plug @ 40' w/ 8 5/8 cementing Plug 1 sac shells and 10 sac cement - Circulate 10 sac in rat and 10 sac in mouse hole.

Plugging Proposal Received by \_\_\_\_\_ (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2:30 PM Day: 13 Month: 2 Year: 19 85

ACTUAL PLUGGING REPORT

1st Plug 2170 w/ 25 sacs

2nd Plug 1340 w/ 110 sac and 1 sac flocc oil

3rd Plug 280 w/ 40 sac

4th Plug 40' w/ 8 5/8 plug 1 sac shells and 10 sac

Rat hole 10 sac - mouse hole 10 sac - cemented by aches Company

Remarks: \_\_\_\_\_ (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Gilbert P. Leiker (TECHNICIAN) 2-22-85

2-26-85

7134

MAR 15 1985

2-13