

4-070178

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-22,797-0000

Approx.

N2 SW NE ~~W2 SE NE~~ /4 SEC. 27, 09 S, 24 W
RT 3300 3710 feet from S section line
KLL 990 1970 feet from E section line

Operator license# 9860

Lease: D. Nickelson Well # 1-27

Operator: Castle Resources/
Ron's Oil Operations

County: Graham

134.06

Address: P.O. Box 87
Schoenchen, Ks 67667

Well total depth 4125 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 209 feet

ABAND. oil well, Gas well, Input well, SWD., D&A X

Plugging contractor: Vonfeldt Drilling, Inc. License# 9431

Address: P.O. Box 611 - Russell, Kansas 67665-0611

Company to plug at: Hour: A.M. Day: 4 Month: June Year: 2000

Plugging proposal received from: Bill Owen

Company: Vonfeldt Drilling, Inc. Phone: 785-483-1684

Were: Ordered 200 sxs 60/40 pozmix - 6% gel - 1/4 Floseal per sack. One 8 5/8" wiper plug.
Spot plugs through drill pipe with heavy drilling mud between all plugs.

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 6:00 A.M. Day: 4, Month: June, Year: 2000

Actual plugging report: No ar buckle cut.

1st Plug at 2200' w/25 sxs. Anhy at 2184' - 2216'.

2nd Plug at 1050' w/100 sxs. Dakota base at 1050'.

3rd Plug at 259' w/40 sxs. Surface pipe at 209' + 50'.

4th Plug at 40' w/10 sxs. One 8 5/8" wiper plug.

Rathole with 15 sxs.

Mousehole with 15 sxs.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: 2525 GL

I did [] / did not [X] observe the plugging.

Richard Williams

INVOICED
DATE 6/14/00
Q1863

100

RECEIVED
STATE CORPORATION COMMISSION
6-9-00
JUN 9 2000

(R)

CONSERVATION DIVISION
Wichita, Kansas