

To: 6 031562
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-065-02157-0001
API NUMBER 15- 1964 D-11,211

SW SW SE, SEC. 28, T 9 S, R 24 W/
330 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6568
Operator: Kaiser-Francis Oil Co.
Name & Address: P.O. Box 666
Ellinwood, Kansas 67526

Lease Name Kohart Well # 1 SWD
County Graham
Well Total Depth 2226 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 222

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated This report is to replace, lost, original report. *sure*

Plugging Contractor B J Titan License Number _____
Address Hays, Kansas

Company to plug at: Hour: _____ A.M. Day: 2 Month: 6 Year: 19 89

Plugging proposal received from John Glenn

(company name) Kaiser-Francis (phone) _____

were: 8 5/8 set @ 222' w/175 sx. cwc. 4 1/2 set @ 2200' w/575 sx. cwc. PBSD 2100'

Perf. 1896' - 1923'. Order work string. Order 225 sx. 65/35 poz. 10% gel.

500# hulls. B.J. Titan - M & L Water Trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:00A.M. Day: 2 Month: 6 Year: 19 89

ACTUAL PLUGGING REPORT Ran tubing to 1560' circulated cement blend. Laid down tubing,
squeezed 4 1/2" casing w/total of 225 sx. cement blend w/350# hulls in last 100 sx.

To max. P.S.I. 1000#. Close in P.S.I. 1000#.

RECEIVED
STATE CORPORATION COMMISSION
7-24-91
JUL 24 1991

Remarks: _____
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Note - Agent plugging report
does not match company
report re: amount of
cement used.

J.P.S.

Signed Carl Goodrow
(TECHNICIAN)