

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20339-00-00  
Spot: CSWSWNW Sec/Twnshp/Rge: 28-9S-24W  
2970 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: HOETING Well Number: 1  
County: GRAHAM Total Vertical Depth: 4155 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 4147 175 SX CMT  
Surface Casing Size: 8.625 feet: 237 150 SX CMT

*\$135.04*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/02/2003 10:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 285 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Perforated 1075' and 2225'.  
Plug through tubing.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 04/02/2003 12:45 PM KCC Agent: DARREL DIPMAN

**Actual Plugging Report:**

Perfs 4061' - 4067'. PBTD 4110'. Squeezed at 2814' w/150 sxs in 1984.  
Casing leak at 2963'.  
8 5/8" surface pipe set at 237' w/150 sxs cement.  
4 1/2" production string set at 4147' w/175 sxs cement.  
Perforated 4 1/2" casing at 1075' and 2225'.  
Ran tubing to 2900' - pumped 80 sxs cement and 300# hulls.  
Pulled tubing to 1120' - pumped 60 sxs cement and 100# hulls. Cement to surface.  
Pulled tubing to surface. Connected to 4 1/2" casing and pumped 70 sxs cement.  
Max. P.S.I. 700#. S.I.P. 200#.  
Connected to 8 5/8" surface casing. Pumped 75 sxs cement.  
Max. P.S.I. 100#. S.I.P. 50#.

RECEIVED  
4-18-03  
APR 18 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

*Darrel Dipman*

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE

4-21-03

WV. NO.

2003061424

APR 07 2003

DON E. PRATT #1 HOETING 28-9-24W  
 HAYS, KANSAS SW SW NW  
 CONTR L. J. DREILING & SONS, INC CTY GRAHAM

GEOL DICK GREEN FIELD GLEN DALE SW

E 2551 KB. CM 6/10/70 <sup>CARD</sup> ISSUED 7/16/70 IP P 135 BOPD (+) 25% WTR  
 LKC 4061-67  
 GR 42.2

API 15-065-20,339

| LOG        | TOPS | DEPTH | DATUM |   |
|------------|------|-------|-------|---|
|            |      |       |       | 8 5/8" 237/150sx; 4 1/2" 4147/175sx   |
| * ANHY     |      | 2210  | + 341 | DST(1) 3876-3922/1', 1650'MGSOCW, BHP 970-970#/30",<br>FP 79-774#   |
| * B ANHY   |      | 2250  | + 301 | DST(2) 3922-3950/1', 240'GIP, 300'MCGO, 550'G & OCW,<br>BHP 488-493#, FP 35-377#  |
| HEEB       |      | 3843  | -1292 |   |
| TOR        |      | 3866  | -1315 | DST(3) 3946-3990/2', 270'THIN M, BHP 586-577#, FP 35-<br>159#   |
| LKC        |      | 3880  | -1329 |   |
| BKC        |      | 4111  | -1560 | DST(4) 3997-4056/2', 120'SOCM, BHP 604-586#, FP 44-88   |
| RTD        |      | 4155  | -1604 | DST(5) 4049-96/2', 150'GIP, 390'OCM, BHP 1118-1051#,<br>FP 35-230#  |
| * SMP TOPS |      |       |       | MICT SWB DWN CO 4110 TD PF 4061-67 SWB DWN A500(15%<br>REG) SWB DWN & SWB OIL 1000'OB SWB 16BO OVER LD SWB<br>21 BO PLUS TR WTR 1ST HR, 23 1/2 BO PLUS TR WTR 2ND, 3RD<br>& 4TH HRS SD/12 FU 1500'WTR (1 1/2 BW ON BTM), POP & P 90<br>BO/22HRS 7 1/2 SPM |

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS