

4-031749

9-4

219  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-20,534-0000

NE SW  
ZT ~~E2 W2~~ NE /4 SEC. 29, 09 S, 24 W  
KCC 3630 feet from S section line  
1650 feet from E section line

Operator license# 30606

Lease Hoeting well # 2-7

Operator: Murfin Drilling Co., Inc.

County Graham

Address: 250 N. Market #300  
Wichita, Kansas 67202

Well total depth 4140 feet <sup>134.55</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 254 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: B.J. Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 4 Month: September Year: 92

Plugging proposal received from: John

Company: Murfin Drilling Co., Inc. Phone:                     

Were: Order 250 sx. 65/35 pozmix - 10% gel. - 500# hulls.  
Hole open to perf's. wireline.  
Shots @ 2028' and 1300'.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 11:00A.M., Day: 4, Month: September, Year: 92

Actual plugging report: 8 5/8" set @ 254' w/185 sx. cwc. 4 1/2" set @  
4139' w/225 sx. Perf. 3906' - 4070'. Squeezed 4 1/2" w/250 sx. cement  
blend with 400# hulls mixed in to Max. P.S.I. 500#. Close in P.S.I.  
150#. Squeezed 8 5/8" w/100 sx. cement blend w/100# hulls mixed in to  
Max. P.S.I. 300#. Close in P.S.I. 150#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD X BAD      Any plug: YES X NO       
Bottom plug(in place): YES     , CALC X, NO      Dakota plug: YES X NO       
Plugged through TUBING     , CASING X. Elevation: 2533 GL     

I did X / did not [      ] observe the plugging.

Carl Goodrow

(agent)

DATE OCT 13 1992  
INV. NO. 36478

STATE CORPORATION COMMISSION  
RECEIVED  
9-24-92  
SEP 24 1992  
CONSERVATION DIVISION  
Wichita, Kansas