

4-031748

9-4

220
P

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-20,361-0000

NE NE SE /4 SEC. 29, 09 S, 24 W
2310 feet from S section line
330 feet from E section line

Operator license# 30606

Lease Hoeting well # 2-2

Operator: Murfin Drilling Co., Inc.

County Graham

Address: 250 N. Market #300
Wichita, Kansas 67202

Well total depth 4150 feet ^{134.87}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 258 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: B.J. Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 4 Month: September Year: 92

Plugging proposal received from: John

Company: Murfin Drilling Co., Inc. Phone:

Were: Order 225 sx. 65/35 pozmix - 10% gel. - 500# hulls.
Hole open to 3800' C.I.B.P.
Shots @ 2220' and 1300'.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 3:30P.M., Day: 4, Month: September, Year: 92

Actual plugging report: 8 5/8" set @ 258' w/160 sx. cwc. 4 1/2" set @
4136' w/225 sx. Perf. 4016' - 4079'. C.I.B.P. @ 3800'. Ran tubing
to 2650'. Spotted cement blend to surface. Laid down tubing.
Squeezed 4 1/2" with total 100 sx. cement blend w/200# hulls mixed in to
Max. P.S.I. 500#. Close in P.S.I. 500#. Squeezed 8 5/8" w/15 sx.
cement blend. Blew out welded head plate @ 500 P.S.I. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

9-24-92
SEP 24 1992

Remarks:

Condition of casing(in hole): GOOD X BAD Any plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

CONSERVATION DIVISION
Wichita, Kansas

I did X did not observe the plugging. Carl Goodrow

Carl Goodrow

DATE OCT 16 1992

(agent)

INV. NO. 36477