

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20351-00-00  
Spot: NESENE Sec/Twnshp/Rge: 29-9S-24W  
3630 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: HOETING Well Number: 2-1  
County: GRAHAM Total Vertical Depth: 4140 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 3992 200 SX CMT  
Surface Casing Size: 8.625 feet: 251 165 SX CMT

*B 134*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/16/2003 9:30 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Casing leak at 2963'. Squeeze at 1984' and 2814' w/150 sxs cement.  
Perforated at 2225' and 1075'.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/16/2003 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated at 2225' and 1075' - two holes.  
Ran tubing to 3013'.  
Allied pumped 185 sxs cement with 300# hulls - cement circulated.  
Pulled tubing out of hole.  
Squeezed with 40 sxs cement and 200# hulls.  
Max. P.S.I. 500#. S.I.P. 500#.  
Hooked up to backside - pumped 75 sxs cement.  
Max. P.S.I. 200#. S.I.P. 100#.

RECEIVED  
6-23-03  
JUN 23 2003  
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS GEORGE NICKELSON #1. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

*110*

Signed

*Richard Williams*

(TECHNICIAN)

INVOICED

DATE 6-24-03

INV. NO. 2063061669

JUN 17 2003

