

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20448-00-00
Spot: CSESESW Sec/Twnshp/Rge: 30-9S-24W
330 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: REYNOLDS Well Number: 1
County: GRAHAM Total Vertical Depth: 4111 feet

Operator License No.: 30076
Op Name: A & A PRODUCTION
Address: PO BOX 100
HILL CITY, KS 67642

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 234 200 SXS CMT
Production: Size 4.5 feet: 4111 100 SXS CMT
Liner: Size feet:
8/33.61

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/04/2001 8:00 AM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 8 yards Redi-Mix.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 04/04/2001 9:00 AM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 234' w/200 sxs cwc. 4 1/2" set at 4111' w/175 sxs.
Prod. Perfs 3900' - 4067'.
Three shots recovered 1000' of 4 1/2" casing.
Loaded hole with 8 yards Redi-Mix (10 yards by yield)
Plug complete.

INVOICED
DATE 5-01-01
INV. NO. 2001061741

RECEIVED
KANSAS CORPORATION COMMISSION
5-1-01
MAY 1 2001
CONSERVATION DIVISION

Remarks:

Plugged through: CSG

District: 04

Signed Carl Goodrow
(TECHNICIAN)

DREILING OIL, INC. #1 REYNOLDS 30-9-24W
 VICTORIA, KANSAS SE SE SW
 CONTR DREILING OIL, INC. CTY GRAHAM

GEOL FIELD DREIL

E 2538 KB CM 5/24/71 ^{CARD} ISSUED 7/29/71 IP P 80 BOPD + 5% WTR
 LANS 3900-05, 3943-47, 4062-67 (GR 38)
 API 15-065-20,448

LOG	TOPS	DEPTH	DATUM	
				8 5/8" 234/200sx; 4 1/2" 4110/100sx
SC		2188	+ 350	DST(1) 3851-77/1', 510'w/s.o., BHP 1052-1005#/30", FP 48-298#
TOP		3602	-1064	DST(2) 3894-3908/1', 2510'GIP, 1220'GSY GIL, BHP 1014-946#/30", FP 120-145#
HEEB		3821	-1283	
ICR		3844	-1306	DST(3) 3937-51/1', 70'OCM, BHP 1027-1003#/30", FP 18-32#
LANS		3856	-1318	DST(4) 3998-4028/1', 10'M, BHP 580-113#/30", FP 26-26#
BKC		4092	-1554	DST(5) 4025-71/1', 15'M/SP OIL, BHP 327-96#/30", FP 48-48#
LTD		4112	-1574	MICT, PF 3900-05, 3943-47, 4062-67
RTD		4115	-1577	3000 ACID SWB LD & SWB 10BOPH/6HRS, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS