

3 - 15-065-20629-0000

6 031508

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1973

C S/2 S/2 SEC. 30, T 9 S, R 24 W/E

330 <sup>27 KCC</sup> feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5145

Lease Name Reynolds Well # 3

Operator: Dreiling Oil Inc.

County Graham 133.57

Name & Address Box 1000

Well Total Depth 4110 feet

Victoria, Ks. 67671

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number

Address Russell, Ks.

Company to plug at: Hour: AM Day: 8 Month: Mar Year: 19 91

Plugging proposal received from

(company name) (phone)

were: 8 5/8 set at 250 w/200 sks cwc. 4 1/2 set at 4107 w/225 sks. PBTD 4071

Perf 3899 - 4066. Order 350 sks 65/35 poz 10% gel 500 lb.s hulls.

Allied Cement Co. Company water trucks. Shots at 2200 anhy 1340 Kiowa. Wireline ran to perf. Holeopen.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10:30AM Day: 8 Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT Sq 4 1/2 casing w/250 sks cement blend w/

500 lbs. hulls mixed into max psi 1000 lbs. Close in psi 800 lbs.

Sq 8 5/8 w/100 sks cement blend to max psi 700 lbs. Close in psi 350 lbs.

Plug complete.

RECEIVED STATE CORPORATION COMMISSION  
4-4-91  
APR 14 1991

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-11-91

INV. NO. 31474

G. S.

Signed Carl Goodrow (TECHNICIAN) Carl Goodrow