

To: 6030838  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-065-21,774-0000  
S. N. 33, SEC. 33, T. 9 S. R. 24 W1/4  
1650 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033  
Operator: MURFIN DRUG. CO.  
Name & Address 230 N. WATER ST. 300  
WICHITA, KANSAS  
67202

Lease Name CHATELAIN Well # B-2  
County GRAHAM 135.04  
Well Total Depth 4155 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 350'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor HALLIBURTON SERVICES License Number \_\_\_\_\_  
Address HAYS KANSAS

Company to plug at: Hour: AM Day: 31 Month: 12 Year: 19 86

Plugging proposal received from PAT CANADAY  
(company name) MURFIN DRUG. CO. (phone) \_\_\_\_\_

were: 8 5/8 SET @ 350' cwc 4 1/2 SET @ 4151 4/NA TOPPER 4046'  
SQUEEZED @ 3803' W 35SX. 1000# ORDER 250 SX. ECONALITE 65/35 FOR  
10% GEL 2 1/2 BICEI HALLIBURTON SERVICES MURFIN WEIRBACK  
WATER TRUCKS

STATE CORPORATION COMMISSION  
1-21-87  
JAN 21 1987  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Carl Goodnow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:AM Day: 31 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT MIX & Pump Down 4 1/2 20 bbl CMT SLURRY (40 SX.)  
5 HULLS MIXED IN WITH CMT. MIX. SLURRY 180 SX. CMT MIX. 4 HULLS = 100 bbl  
WATER TO MIX. MAX. PSI 800# CLOSE IN 150#  
MIX. & Pump Down 8 5/8 - 4 1/2 ANNULUS 1 SX. HULLS 70 SX. CMT. MIX. 40 bbl  
WATER TO MIX. MAX. 500# PSI CLOSE IN. 150# PSI. PLUG. COMPLETE

Remarks: Discussed @ Dan B & D. Anderson 1-21-87  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(If added) observe this plugging.

DATE 1-21-87  
INV. NO. 15974  
12-31

Signed Carl Goodnow  
(TECHNICIAN) DB