

10-8-87 15-065-01624-0000

6 030970

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1961

SW NW NW, SEC. 1, T 9 S, R 25

TECHNICIAN'S PLUGGING REPORT

Operator License # 9524

Operator: Tom Weems
Name & Address: Gypsy Drilling Co.
Box 2558
Hutchinson, Kansas 67501

4290 feet from S section line
4950 feet from E section line

Lease Name Minium Well # 1

County Graham 138.29

Well Total Depth 4255 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 156

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Gypsy Drilling Co. License Number 9524

Address Hutchinson, Kansas

Company to plug at: Hour: PM Day: 8 Month: Oct. Year: 19 87

Plugging proposal received from Tom Weems

(company name) Gypsy Drilling Co. (phone)

were: 8 5/8" at 156' cwc 5 1/2" set at 4120'. Perf. 4010' - 16'.

Perf at 1400' three shots at 2207' Anhy. Order 300 sks 65/35 Poz 10% Gel 2% Dicel Cement Blend 10 sks Hulls. Allied Cement Co. Wellbrock John Keith Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:00P. Day: 8 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT 5 1/2" casing open and dry to bottom. Squeezed 5 1/2" casing w/200 sks cement Blend w/7 sks Hulls Mixed in max Psi 300#. Close in Psi 150#.

Squeeze 8 5/8" - 5 1/2" casing Annulus w/100 sks Cement Blend w/3 sks Hulls mixed in.

Max Psi 200# Close in Psi 150# Plug complete.

11-30-87
15 30 97

Remarks: (If additional description is necessary, use BACK of this form.)

I (could) observe this plugging.

DATE 12-7-87

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow

INV. NO. 19148
10-8

JAN 14 1988 MAR 03 1988 SEP 12 1988 MAY 02 1990
FORM CP-2/3 Rev. 01-84 LR