

4-060947

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

8-18

API Number: 15-065-22,773 - 0000
150' N. of
SE SE NE /4 SEC. 05, 09 S, 25 W
3120 feet from S section line
330 feet from E section line

Operator license# 30163
Great Plains Petro. Inc. ^{2T} KCC
Operator: Rod A. Phares

Lease: Dreiling Well # 3
County: Graham 141.79

Address: 1902 E. Waterman
Wichita, Kansas 67211

Well total depth 4363 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 247 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Mallard JV License# 4958

Address: McPherson, Kansas 67460

Company to plug at: Hour: 5:00 A.M. Day: 18 Month: August Year: 1996

Plugging proposal received from: Carol

Company: Mallard JV Phone:

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.
Space all plugs with heavy drilling mud through drill pipe.

8-26-96

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 7:00 A.M., Day: 18, Month: August, Year: 1996

Actual plugging report:

- 1st. Plug at 2250' w/25 sxs. - Anhydrite 2227' - 2267'.
- 2nd. Plug at 1350' w/100 sxs. - Surface pipe to 247'.
- 3rd. Plug at 300' w/40 sxs. - Dakota 1038' - 1338'.
- 4th. Plug at 40' w/10 sxs.
- Rathole with 15 sxs.
- Mousehole with 10 sxs.

Remarks: Allied Cementing.


Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: 2538 GL

I did / did not [X] observe the plugging.

INVOICE
DATE AUG 28 1996
INV. NO. 43678


(agent)
DK Form CP-2/3

8-18 NOV 04 1996