

4-060962

8-27

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-20,555 - 0000

E2 SE NW /4 SEC. 17, 09 S, 25 W
3300 feet from S section line
2970 feet from E section line

Operator license# 5364

Lease Pfeifer Well # 1

Operator: Beren Corporation

County: Graham 134.87

Address: P.O. Box 723
Hays, Kansas 67601

Well total depth 4150 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 258 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Co Tools License#

Address:

Company to plug at: Hour: 10:00 A.M. Day: 27 Month: August Year: 1996

Plugging proposal received from: Bob Grant

Company: Beren Corporation Phone: 913-628-6101

Were: Order 290 sxs 60/40 posmix - 10% gel - hulls - 15 sxs gel.
Plug with tubing.
No recorded casing squeezes.

RECEIVED
STATE CORPORATION COMMISSION
9-13-96
SEP 13 1996

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 8:00 P.M., Day: 27, Month: August, Year: 1996

Actual plugging report: 8 5/8" to 258' with 150 sxs. 5 1/4" to 4148' with 100 sxs. Perfs at 4081' - 4084', 3931'- 3935'. Perforated at 1450' and 2315'. Ran tubing to 4117' and pumped 15 sxs gel, followed by 50 sxs cement with 400# hulls and displaced to 2300'. Pulled tubing to 2308' and circulated cement with 165 sxs cement with 200# hulls. Pulled tubing. Tied onto production casing and pumped 20 sxs cement. Max. P.S.I. 500#. S.I.P. 500#. Tied onto annulus but severely corroded. Cut off head and welded on a plate with collar. September 5, 1996 - Tied onto surface pipe and pumped 25 sxs cement. Pressured up to 400# and blew out casing.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: 2623 GL

INVOICED
I did [9] (did not [X] observe the plugging.
DATE 9-16-96
INV. NO. 46499
8-27

[Signature]
(agent)
Form CP-2/3