

15-065-01065-0001

4-060957

D-16,747

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

8-29 API Number: 15- -

NE NW /4 SEC. 17, 09 S, 25 W
4620 feet from S section line
3300 feet from E section line

Operator license# 5364

Lease Pfeifer OWWO Well # 1

Operator: Beren Corporation

County: Graham

Address: P.O. Box 723
Hays, Kansas 67601

Well total depth 2108 68.51 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 232 feet

Aband. oil well, Gas well, Input well, SWD X, D & A

Plugging contractor: Co Tools License#

Address:

Company to plug at: Hour: 9:00 A.M. Day: 29 Month: August Year: 1996

Plugging proposal received from: Bob Grant

Company: Beren Corporation Phone: 913-628-6101

Were: Order 250 sxs 60/40 posmix - 10% gel - hulls.
Plug with tubing.

RECEIVED
KANSAS CORPORATION COMMISSION
9-6-96
SEP 06 1996

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

CONSERVATION DIVISION
WICHITA, KS

Completed: Hour: 3:00 P.M., Day: 29, Month: August, Year: 1996

Actual plugging report: 8 5/8" to 232' w/150 sxs. 5 1/2" to 2108' cwc with 500 sxs. Perfs at 2025' - 2065'. Tubing fish at 1618'. Ran tubing to 1611'. Circulated cement to surface with 150 sxs with 350# hulls. Pulled tubing. Tied onto production casing and pumped 50 sxs cement with 150# hulls with cement to surface in annulus. Shut in annulus and pumped 100 sxs cement. Max. P.S.I. 450#. S.I.P. 100#.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING. Elevation: GL

I did / did not [X] observe the plugging.

[Signature]
DH (agent)
Form CP-2/3

INVOICED
DATE SEP 09 1996
INV. NO. 46442